



WICHITA, KANSAS

ADDENDUM NO. 2
TO THE PROPOSAL FB640184

Commerce Rail Yard Parking Lot
(East of Commerce, south of Waterman)

472-84935 210494

TO BE BID: September 23, 2016

The following changes and additions shall be made to the plans and proposal.

1. **Pipe, SWS, PVC 4”, Perforated.** Deleted bid item. This item shall be bid subsidiary to the **Stage Construction** bid item.
2. **Working Days/Completion Date.** All work on the project except for placement of artistic elements shall be completed by **December 19, 2016.**
3. **Sheet E-1 – Light Fixture Schedule Notes:**
 - a. FIXTURE A: PROVIDE 1 STRAND OF EACH...”equals 100 emitters or 40.5’ strand per each of Amber, Red, Blue, Green and White
 - b. FIXTURE B: PROVIDE 1 STRAND OF EACH...”equals 100 emitters or 40.5’ strand per each of Amber, Red, Blue, Green and White
 - c. FIXTURE C: PROVIDE 12’ STRAND OF AMBER...”equals 39 emitters or 12’ strand of Amber per each of 20 Rail-Grass Units
4. **Sheet E-1 – Detail A:**
 - a. Item #6 – shall be an Intermatic #ET2825CP astronomical time switch programmed per Artist requirements
 - b. Item #7 – shall be a Mean Well #HLG-150H-12A Power supply in quantity indicated in lieu of that shown.
 - c. Five 120 volt DPST ice cube relays shall be added to the diagram before each control switch 1, 2, 3, 4, and 10 to be activated from hot wire from motion sensor when motion sensor is activated. When activated, this relay will bypass each respective control switch. This will put power to all lights when motion sensor is activated.
 - d. All relays to be wired and programmed for “interval” operation and set as required by Artist.
5. **Sheet E-2 – Plan Notes**
 - a. Plan Note #2 – Artist will install lighting element (LED strands and custom housings) at this location.
6. **Sheet E-3 – Plan Notes**
 - a. Plan Note #3 – “6’ on each side” both sides totaling 12’.

- b. Plan Note #5 – Contractor to provide Mean Well #hLG-150H-12 A Power supply in quantity indicated in lieu of that shown.

7. **Tracks and Rail Tie Removal:**

- a. Contractor shall remove rails so as not to bend, break or distort rail.
- b. Kent Williams or his designated representative will be present to select rails removed for re-use as Rail-Grass Sculpture.
- c. Contractor shall remove excessive dirt and debris from rails selected for re-use, and transport to Hall Industrial Services, 1211 E. Murdock St. Wichita, KS 67214. Coordinate with Kent Williams or his designated representative.
- d. Rails selected for disposal shall be transported from job site and disposed of by contractor.

****For vendors not submitting bids online, the revised Solicitation form can be obtained from QuikPrint at 316-942-2208.****

Each bidder is required to acknowledge receipt of this Addendum by his signature affixed hereto and to file same with and attached to his bid. Any Bid Proposal that is returned without all addenda signed and included in the Proposal shall be considered an invalid Proposal.

September 21, 2016

Gary Janzen, P.E.
City Engineer

Date _____

Signature of Bidder

BIDDER: _____
(print or type name of firm)

ADDRESS: _____

AUTHORIZED AGENT: _____
(Signature)

(print or type name of authorized agent)